


2 SITE PLAN - DPOS  
A201.7



1 GROUND FLOOR sheet DPOS  
A201.7

**PARKING NOTES PER CITY OF HAMILTON BY-LAW 05-590:**  
 1. MINIMUM PARKING SPACE SIZES (UNLESS OTHERWISE NOTED):  
 - 2800mm WIDE X 5800mm LONG (NO SIDES OBSTRUCTED)  
 - 3100mm WIDE X 5500mm LONG (ONE SIDE OBSTRUCTED)  
 - 3400mm WIDE X 5800mm LONG (TWO SIDES OBSTRUCTED)  
 - 4400mm WIDE X 5500mm LONG (ACCESSIBLE PARKING)  
 2. MAINTAIN MINIMUM DRIVE AISLE WIDTH OF 6000mm UNLESS OTHERWISE NOTED.  
 3. MAINTAIN MINIMUM HEADROOM CLEARANCE OF 2100mm THROUGHOUT.

**PARKING LEGEND:**


- ⊙ COMMERCIAL PARKING SPACE
- ⊙ RESIDENTIAL PARKING SPACE
- ⊙ VISITOR PARKING SPACE
- ⊙ EXISTING PARKING SPACE
- ⊙ BIKE LOCKER
- ⊙ BIKE PARKING (STACKED)
- ⊙ BIKE PARKING (VERTICAL)
- ⊙ CONVEX MIRROR
- ⊙ ELECTRIC VEHICLE
- ⊙ LIGHT STANDARD
- ▨ PAINTED LINES
- ▨ FIRE-RATED BULKHEAD

TYPICAL ONE SIDE OBSTRUCTED TWO SIDE OBSTRUCTED TYPE C MOVING ACCESSIBLE ACCESSIBLE VISITOR - TYPE A ACCESSIBLE VISITOR - TYPE B ADA COMPLIANT

Date	No.	Description
2024-02-21		Draft Plan of Subdivision Resubmission

REVISION RECORD	

ISSUE RECORD	



**BDP. Quadrangle**

Quadrangle Architects Limited  
 The Wool, 8 Spadina Avenue, Suite 2100, Toronto, ON M5V 0S9  
 416-598-1342 www.bdpquadrangle.com

Eastgate Square Master Plan  
 75 Centennial Parkway North,  
 Hamilton, Ontario  
 for Harrison Equity Partners

21043 As indicated/V  
 PROJECT SCALE DRAWN REVIEWED

Site and Ground Floor Plan for DPOS

**A201.7**

Note: This drawing is the property of the Architect and may not be reproduced or used without the expressed consent of the Architect. The Contractor is responsible for checking and verifying all sizes and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.